KERALA STATE ROAD TRANSPORT CORPORATION

TRANSPORT BHAVAN, FORT, THIRUVANANTHAPURAM - 695 023
Telephone No: 0471-2471011, (Extn: 236 / 231 / 321)
E-mail: sr@kerala.gov.in Web: www.keralartc.com

No. S001-SRA05/114/2026-STORE-KSRTC-HQ **Date: 04.11.2026**

RE-QUOTATION NOTICE

KSRTC is inviting Quotation for the Supply, installation and commissioning of Inverter type Split Room Air Conditioner 1.5 Ton at KSRTC Transport Bhavan, Fort, Thiruvananthapuram (Fourth Floor, Cash Section)

Sealed Quotation should reach the office of the Chairman and Managing Director, Kerala State Road Transport Corporation before 13.00 Hrs **on 10.11.2026 and it will be opened at** 15.00 Hrs**. on the same day.** There shall not be more than one financial offer in a financial bid for one item. Offering more than one brand / model will make the bid invalid.

SL. No.	Items Required with Specifications	Quantity
1.	**Inverter Type Split Room Air Conditioner : 1.5 Ton** 5-Star Inverter Split AC with variable-speed compressor, R-32 refrigerant or latest equivalent, 230 V single-phase supply, including a suitable voltage stabilizer for protection against over-voltage and under-voltage, along with compressor protection. Complete with copper piping, insulation, drain pipe, cables, remote control, outdoor stand and installation accessories. The unit shall conform to applicable BEE and BIS standards. Warranty: Minimum 5 years for PCB/electronic components and 10 years for compressor.	**1 No.**

1. The rates quoted should be for the supply (including freight and unloading charge), installation and commissioning of Inverter type split room Air Conditioner at KSRTC, Transport Bhavan, Fort, Thiruvananthapuram - 695023 (Cash Section, Fourth Floor)
2. **The bidder shall visit KSRTC, Transport Bhavan, Fort, Thiruvananthapuram - 695023 (Cash Section, Fourth Floor) for accessing the requirement of extra accessories required for installation and commissioning of** Inverter type Split Room Air Conditioner.

3. Quotation should contain the make, brand and name of manufacturer. There shall not be more than one brand offer.
4. The payment will be made only after supply, installation, commissioning and satisfactory working of Air Conditioner at KSRTC, Transport Bhavan, Fort, Thiruvananthapuram (Cash Section, Fourth Floor).
5. Quotations will be opened at **15.00 hours** on **10.11.2026** in the presence of the bidders or their authorized nominees available at the time of opening.
6. Supply and installation should be completed within 5 days from the date of purchase order, failing which the corporation will procure the materials from other sources at the risk and cost of the bidder.
7. No enhancement of rates once accepted will be considered.
8. Delivery position should be clearly noted by the bidder.
9. The successful bidder should be willing to provide warranty
10. The corporation may reject any or all the supplies which are not suitable as per tender specifications.
11. Quotation should be submitted in sealed covers duly prescribing on the cover with following details.

Quotation for the Supply of: **Inverter Type Split Room Air Conditioner 1.5 Ton**
Tender No. : **S001-SRA05/114/2026-STORE-KSRTC-HQ**
Opening Date : **10.11.2026**

For Tender Inviting Authority

PROFORMA

Sl No	*Particulars of item required with specification* ***There shall not be more than one financial offer for one item in a financial bid***	*Basic Price for* 1 No. in Rs	**Discount** in Rs & in %	*GST* in Rs & in %	*End rate for* 1 No. in Rs
1	1.5 Ton, 5-Star Inverter Split AC with variable-speed compressor, R-32 refrigerant or latest equivalent, 230 V single-phase supply, including a suitable voltage stabilizer for protection against over-voltage and under-voltage, along with compressor protection. Complete with copper piping, insulation, drain pipe, cables, remote control, outdoor stand and installation accessories. The unit shall conform to applicable BEE and BIS standards.				
2	Cost of extra accessories required for installation of one AC				
3	Installation and Commissioning Charges for one AC				
	End rate for supply, installation and Commissioning of One AC in Rs.				

1 (a)	**1.5 Ton Inverter Type Split Room Air Conditioner**	Make	
		Brand	
		Model	
		Warranty	
1 (b)	**Stabilizer Capacity**		
	Make		
	Brand		
	Model		
	Warranty		
1 (c)	**Details of accessories offered**		

Signature

Place:

Date: (Office Seal)

Name & Full Address of the Bidder